


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT <input type="checkbox"/>				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Gilbert 14-34-2-4W				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT ALTAMONT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Patented			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Newfield RMI LLC						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-823-1932				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 1001 17th Street, Suite 2000, ,						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		301 FSL 2085 FWL		SESW	34	2.0 S	4.0 W	U		
Top of Uppermost Producing Zone		660 FSL 2076 FWL		SESW	34	2.0 S	4.0 W	U		
At Total Depth		660 FSL 2076 FWL		SESW	34	2.0 S	4.0 W	U		
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 301			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 16			26. PROPOSED DEPTH MD: 11862 TVD: 11850				
27. ELEVATION - GROUND LEVEL 5881			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Cond	17.5	14	0 - 60	37.0	H-40 ST&C	0.0	Class G	35	1.17	15.8
Surf	12.25	9.625	0 - 1000	36.0	J-55 LT&C	8.3	Type III	54	3.33	11.0
							Type III	94	1.92	13.0
I1	8.75	7	0 - 9462	26.0	P-110 LT&C	9.5	35/65 Poz	320	3.53	11.0
							50/50 Poz	259	1.29	14.0
Prod	6.125	4.5	9262 - 11850	11.6	P-110 LT&C	11.5	50/50 Poz	121	2.31	14.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent			PHONE 435 719-2018			
SIGNATURE				DATE 10/09/2012			EMAIL starpoint@etv.net			
API NUMBER ASSIGNED 43013517810000				APPROVAL  Permit Manager						

Newfield Production Company
14-34-2-4W
SE/SW Section 34, T2S, R4W
Duchesne County, UT

Drilling Program

1. Formation Tops	TVD	MD
Uinta	surface	surface
Green River	4,610'	4,618'
Garden Gulch member	7,526'	7,538'
Wasatch	10,139'	10,151'
TD	11,850'	11,862'

2. Depth to Oil, Gas, Water, or Minerals	TVD	
Base of moderately saline	2,450'	(water)
Green River	7,526' - 10,139'	(oil)
Wasatch	10,139' - TD	(oil)

3. Pressure Control

<u>Section</u>	<u>BOP Description</u>
Surface	12-1/4" diverter

Interm/Prod The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval (MD)		Weight (ppf)	Grade	Couple	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom							Burst	Collapse	Tension
Conductor 14	0'	60'	37	H-40	Weld	--	--	--	--	--	--
									--	--	--
Surface 9 5/8	0'	1,000'	36	J-55	LTC	8.33	8.33	12	3,520	2,020	453,000
									6.27	6.35	12.58
Intermediate 7	0'	9,462'	26	P-110	LTC	9	9.5	15	9,960	6,210	693,000
									2.23	1.67	2.82
Production 4 1/2	9,262'	11,850'	11.6	P-110	LTC	11	11.5	--	10,690	7,560	279,000
									1.91	1.28	2.03

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Intermediate casing MASP = (reservoir pressure) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	17 1/2	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	41	15%	15.8	1.17
				35			
Surface Lead	12 1/4	500'	Type III	180	15%	11.0	3.33
				54			
Surface Tail	12 1/4	500'	Type III	180	15%	13.0	1.92
				94			
Intermediate Lead	8 3/4	6,526'	65% Class G / 35% Poz + 10% Bentonite	1128	15%	11.0	3.53
				320			
Intermediate Tail	8 3/4	1,936'	50% Class G / 50% Poz + 1% Bentonite	335	15%	14.0	1.29
				259			
Production Tail	6 1/8	2,588'	50% Class G / 50% Poz + 1% Bentonite	280	15%	14.0	2.31
				121			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate and production casing strings will be calculated from an open hole caliper log, plus 15% excess.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 1,000'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.
1,000' - TD	A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and if conditions warrant, with barite. Anticipated maximum mud weight is 11.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run from TD to the base of the surface casing. A compensated neutron/formation density log will be run from TD to the top of the Garden Gulch formation. A cement bond log will be run from PBTD to the cement top behind the production casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.57 psi/ft gradient.

$$11,850' \times 0.57 \text{ psi/ft} = 6778 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.


9. Other Aspects

This is planned as a "S" shaped directional well. See attached directional plan.

Newfield requests the following variances from Onshore Order #2:


- Variance from Onshore Order #2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

T2S, R4W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**

WELL LOCATION, 14-34-2-4W, LOCATED AS SHOWN IN LOT 3 OF SECTION 34, T2S, R4W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, 14-34-2-4W, LOCATED AS SHOWN IN LOT 3 OF SECTION 34, T2S, R4W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

**WELL LOCATION:****14-34-2-4W**

ELEV. UNGRADED GROUND = 5881.3'

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
 REGISTRATION No. 16189377
 STACY W. STEWART
 STATE OF UTAH

NAD 83 (SURFACE LOCATION)
LATITUDE = 40°15'26.90"
LONGITUDE = 110°19'27.11"
NAD 27 (SURFACE LOCATION)
LATITUDE = 40°15'27.06"
LONGITUDE = 110°19'24.55"
NAD 83 (BOTTOM HOLE LOCATION)
LATITUDE = 40°15'30.45"
LONGITUDE = 110°19'27.25"
NAD 27 (BOTTOM HOLE LOCATION)
LATITUDE = 40°15'30.61"
LONGITUDE = 110°19'24.69"

TRI STATE LAND SURVEYING & CONSULTING


180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
 (435) 781-2501

DATE SURVEYED: 06-21-12	SURVEYED BY: C.S.	VERSION:
DATE DRAWN: 06-25-12	DRAWN BY: M.W.	V1
REVISED:	SCALE: 1" = 1000'	

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

Access Road Map



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

14-34-2-4W
3-3-3-4WH
SEC. 34, T2S, R4W, U.S.B.&M.
Duchesne County, UT.


DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	07-05-2012		V1
SCALE:	1:100,000		

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



Legend

- Existing Road
- Previously Proposed Road
- Proposed Road

Total Road Distances

Proposed Road ± 2,508'

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

14-34-2-4W
3-3-3-4WH
SEC. 34, T2S, R4W, U.S.B.&M.
Duchesne County, UT.


DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	07-05-2012		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


14-34-2-4W
3-3-3-4WH
SEC. 34, T2S, R4W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	07-05-2012		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

C



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

14-34-2-4W
3-3-3-4WH
SEC. 34, T2S, R4W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	07-05-2012		V1
SCALE:	1" = 2,000'		




TOPOGRAPHIC MAP

SHEET

D

Newfield Production Company

Project: Vertical
Site: 14-34-2-4W
Well: 14-34-2-4W
Wellbore: Wellbore #1
Design: Design #1



PROJECT DETAILS: Vertical

Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: Alabama Eastern Zone

System Datum: Mean Sea Level

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1000.0	0.00	0.00	1000.0	0.0	0.0	0.00	0.00	0.0	
3	1393.4	3.93	357.42	1393.1	13.5	-0.6	1.00	357.42	13.5	
4	6228.6	3.93	357.42	6216.9	344.9	-15.5	0.00	0.00	345.3	
5	6622.0	0.00	0.00	6610.0	358.4	-16.1	1.00	180.00	358.8	
Ø	1862.0	0.00	0.00	11850.0	358.4	-16.1	0.00	0.00	358.8	BHL

RJ NFX Utah

Vertical

14-34-2-4W

14-34-2-4W

Wellbore #1

Plan: Design #1

Standard Planning Report

07 September, 2012

Newfield Exploration

Planning Report

Database:	EDM5000	Local Co-ordinate Reference:	Site 14-34-2-4W
Company:	RJ NFX Utah	TVD Reference:	RKB @ 5899.0ft (Original Well Elev)
Project:	Vertical	MD Reference:	RKB @ 5899.0ft (Original Well Elev)
Site:	14-34-2-4W	North Reference:	Grid
Well:	14-34-2-4W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Site	14-34-2-4W				
Site Position:		Northing:	1,381,469.08 m	Latitude:	40° 15' 26.900 N
From:	Lat/Long	Easting:	-1,892,440.12 m	Longitude:	110° 19' 27.110 W
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in	Grid Convergence:	0.00 °

Well	14-34-2-4W					
Well Position	+N-S	0.0 ft	Northing:	1,381,469.08 m	Latitude:	40° 15' 27.462 N
	+E-W	0.0 ft	Easting:	-1,892,440.12 m	Longitude:	110° 19' 22.174 W
Position Uncertainty		0.0 ft	Wellhead Elevation:		Ground Level:	0.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	9/7/2012	11.27	65.90	52,269

Design	Design #1				
Audit Notes:					
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0	
Vertical Section:	Depth From (TVD)	+N-S	+E-W	Direction	
	(ft)	(ft)	(ft)	(°)	
	0.0	0.0	0.0	357.43	

Plan Sections										
Measured	Inclination	Azimuth	Vertical	+N-S	+E-W	Dogleg	Build	Turn	TFO	Target
Depth	(°)	(°)	Depth	(ft)	(ft)	Rate	Rate	Rate	(°)	
(ft)			(ft)			(°/100ft)	(°/100ft)	(°/100ft)		
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,393.4	3.93	357.43	1,393.1	13.5	-0.6	1.00	1.00	0.00	357.43	
6,228.6	3.93	357.43	6,216.9	344.9	-15.5	0.00	0.00	0.00	0.00	
6,622.0	0.00	0.00	6,610.0	358.4	-16.1	1.00	-1.00	0.00	180.00	
11,862.0	0.00	0.00	11,850.0	358.4	-16.1	0.00	0.00	0.00	0.00 BHL	

Newfield Exploration

Planning Report

Database:	EDM5000	Local Co-ordinate Reference:	Site 14-34-2-4W
Company:	RJ NFX Utah	TVD Reference:	RKB @ 5899.0ft (Original Well Elev)
Project:	Vertical	MD Reference:	RKB @ 5899.0ft (Original Well Elev)
Site:	14-34-2-4W	North Reference:	Grid
Well:	14-34-2-4W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	1.00	357.43	1,100.0	0.9	0.0	0.9	1.00	1.00	0.00
1,200.0	2.00	357.43	1,200.0	3.5	-0.2	3.5	1.00	1.00	0.00
1,300.0	3.00	357.43	1,299.9	7.8	-0.4	7.9	1.00	1.00	0.00
1,393.4	3.93	357.43	1,393.1	13.5	-0.6	13.5	1.00	1.00	0.00
1,400.0	3.93	357.43	1,399.7	13.9	-0.6	14.0	0.00	0.00	0.00
1,500.0	3.93	357.43	1,499.4	20.8	-0.9	20.8	0.00	0.00	0.00
1,600.0	3.93	357.43	1,599.2	27.6	-1.2	27.7	0.00	0.00	0.00
1,700.0	3.93	357.43	1,699.0	34.5	-1.6	34.5	0.00	0.00	0.00
1,800.0	3.93	357.43	1,798.7	41.4	-1.9	41.4	0.00	0.00	0.00
1,900.0	3.93	357.43	1,898.5	48.2	-2.2	48.3	0.00	0.00	0.00
2,000.0	3.93	357.43	1,998.3	55.1	-2.5	55.1	0.00	0.00	0.00
2,100.0	3.93	357.43	2,098.0	61.9	-2.8	62.0	0.00	0.00	0.00
2,200.0	3.93	357.43	2,197.8	68.8	-3.1	68.8	0.00	0.00	0.00
2,300.0	3.93	357.43	2,297.6	75.6	-3.4	75.7	0.00	0.00	0.00
2,400.0	3.93	357.43	2,397.3	82.5	-3.7	82.6	0.00	0.00	0.00
2,500.0	3.93	357.43	2,497.1	89.3	-4.0	89.4	0.00	0.00	0.00
2,600.0	3.93	357.43	2,596.8	96.2	-4.3	96.3	0.00	0.00	0.00
2,700.0	3.93	357.43	2,696.6	103.0	-4.6	103.2	0.00	0.00	0.00
2,800.0	3.93	357.43	2,796.4	109.9	-4.9	110.0	0.00	0.00	0.00
2,900.0	3.93	357.43	2,896.1	116.8	-5.3	116.9	0.00	0.00	0.00
3,000.0	3.93	357.43	2,995.9	123.6	-5.6	123.7	0.00	0.00	0.00
3,100.0	3.93	357.43	3,095.7	130.5	-5.9	130.6	0.00	0.00	0.00
3,200.0	3.93	357.43	3,195.4	137.3	-6.2	137.5	0.00	0.00	0.00
3,300.0	3.93	357.43	3,295.2	144.2	-6.5	144.3	0.00	0.00	0.00
3,400.0	3.93	357.43	3,395.0	151.0	-6.8	151.2	0.00	0.00	0.00
3,500.0	3.93	357.43	3,494.7	157.9	-7.1	158.0	0.00	0.00	0.00
3,600.0	3.93	357.43	3,594.5	164.7	-7.4	164.9	0.00	0.00	0.00
3,700.0	3.93	357.43	3,694.3	171.6	-7.7	171.8	0.00	0.00	0.00
3,800.0	3.93	357.43	3,794.0	178.4	-8.0	178.6	0.00	0.00	0.00
3,900.0	3.93	357.43	3,893.8	185.3	-8.3	185.5	0.00	0.00	0.00
4,000.0	3.93	357.43	3,993.5	192.2	-8.6	192.3	0.00	0.00	0.00
4,100.0	3.93	357.43	4,093.3	199.0	-8.9	199.2	0.00	0.00	0.00
4,200.0	3.93	357.43	4,193.1	205.9	-9.3	206.1	0.00	0.00	0.00
4,300.0	3.93	357.43	4,292.8	212.7	-9.6	212.9	0.00	0.00	0.00
4,400.0	3.93	357.43	4,392.6	219.6	-9.9	219.8	0.00	0.00	0.00
4,500.0	3.93	357.43	4,492.4	226.4	-10.2	226.7	0.00	0.00	0.00
4,600.0	3.93	357.43	4,592.1	233.3	-10.5	233.5	0.00	0.00	0.00
4,700.0	3.93	357.43	4,691.9	240.1	-10.8	240.4	0.00	0.00	0.00
4,800.0	3.93	357.43	4,791.7	247.0	-11.1	247.2	0.00	0.00	0.00
4,900.0	3.93	357.43	4,891.4	253.8	-11.4	254.1	0.00	0.00	0.00
5,000.0	3.93	357.43	4,991.2	260.7	-11.7	261.0	0.00	0.00	0.00
5,100.0	3.93	357.43	5,091.0	267.6	-12.0	267.8	0.00	0.00	0.00
5,200.0	3.93	357.43	5,190.7	274.4	-12.3	274.7	0.00	0.00	0.00

Newfield Exploration

Planning Report

Database:	EDM5000	Local Co-ordinate Reference:	Site 14-34-2-4W
Company:	RJ NFX Utah	TVD Reference:	RKB @ 5899.0ft (Original Well Elev)
Project:	Vertical	MD Reference:	RKB @ 5899.0ft (Original Well Elev)
Site:	14-34-2-4W	North Reference:	Grid
Well:	14-34-2-4W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	3.93	357.43	5,290.5	281.3	-12.6	281.5	0.00	0.00	0.00
5,400.0	3.93	357.43	5,390.2	288.1	-13.0	288.4	0.00	0.00	0.00
5,500.0	3.93	357.43	5,490.0	295.0	-13.3	295.3	0.00	0.00	0.00
5,600.0	3.93	357.43	5,589.8	301.8	-13.6	302.1	0.00	0.00	0.00
5,700.0	3.93	357.43	5,689.5	308.7	-13.9	309.0	0.00	0.00	0.00
5,800.0	3.93	357.43	5,789.3	315.5	-14.2	315.9	0.00	0.00	0.00
5,900.0	3.93	357.43	5,889.1	322.4	-14.5	322.7	0.00	0.00	0.00
6,000.0	3.93	357.43	5,988.8	329.2	-14.8	329.6	0.00	0.00	0.00
6,100.0	3.93	357.43	6,088.6	336.1	-15.1	336.4	0.00	0.00	0.00
6,200.0	3.93	357.43	6,188.4	342.9	-15.4	343.3	0.00	0.00	0.00
6,228.6	3.93	357.43	6,216.9	344.9	-15.5	345.3	0.00	0.00	0.00
6,300.0	3.22	357.43	6,288.2	349.4	-15.7	349.7	1.00	-1.00	0.00
6,400.0	2.22	357.43	6,388.0	354.1	-15.9	354.5	1.00	-1.00	0.00
6,500.0	1.22	357.43	6,488.0	357.1	-16.1	357.5	1.00	-1.00	0.00
6,600.0	0.22	357.43	6,588.0	358.4	-16.1	358.7	1.00	-1.00	0.00
6,622.0	0.00	0.00	6,610.0	358.4	-16.1	358.8	1.00	-1.00	0.00
6,700.0	0.00	0.00	6,688.0	358.4	-16.1	358.8	0.00	0.00	0.00
6,800.0	0.00	0.00	6,788.0	358.4	-16.1	358.8	0.00	0.00	0.00
6,900.0	0.00	0.00	6,888.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,000.0	0.00	0.00	6,988.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,100.0	0.00	0.00	7,088.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,200.0	0.00	0.00	7,188.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,300.0	0.00	0.00	7,288.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,400.0	0.00	0.00	7,388.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,500.0	0.00	0.00	7,488.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,600.0	0.00	0.00	7,588.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,700.0	0.00	0.00	7,688.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,800.0	0.00	0.00	7,788.0	358.4	-16.1	358.8	0.00	0.00	0.00
7,900.0	0.00	0.00	7,888.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,000.0	0.00	0.00	7,988.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,100.0	0.00	0.00	8,088.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,200.0	0.00	0.00	8,188.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,300.0	0.00	0.00	8,288.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,400.0	0.00	0.00	8,388.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,500.0	0.00	0.00	8,488.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,600.0	0.00	0.00	8,588.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,700.0	0.00	0.00	8,688.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,800.0	0.00	0.00	8,788.0	358.4	-16.1	358.8	0.00	0.00	0.00
8,900.0	0.00	0.00	8,888.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,000.0	0.00	0.00	8,988.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,100.0	0.00	0.00	9,088.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,200.0	0.00	0.00	9,188.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,300.0	0.00	0.00	9,288.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,400.0	0.00	0.00	9,388.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,500.0	0.00	0.00	9,488.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,600.0	0.00	0.00	9,588.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,700.0	0.00	0.00	9,688.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,800.0	0.00	0.00	9,788.0	358.4	-16.1	358.8	0.00	0.00	0.00
9,900.0	0.00	0.00	9,888.0	358.4	-16.1	358.8	0.00	0.00	0.00
10,000.0	0.00	0.00	9,988.0	358.4	-16.1	358.8	0.00	0.00	0.00
10,100.0	0.00	0.00	10,088.0	358.4	-16.1	358.8	0.00	0.00	0.00
10,200.0	0.00	0.00	10,188.0	358.4	-16.1	358.8	0.00	0.00	0.00
10,300.0	0.00	0.00	10,288.0	358.4	-16.1	358.8	0.00	0.00	0.00
10,400.0	0.00	0.00	10,388.0	358.4	-16.1	358.8	0.00	0.00	0.00

Newfield Exploration

Planning Report

Database:	EDM5000	Local Co-ordinate Reference:	Site 14-34-2-4W
Company:	RJ NFX Utah	TVD Reference:	RKB @ 5899.0ft (Original Well Elev)
Project:	Vertical	MD Reference:	RKB @ 5899.0ft (Original Well Elev)
Site:	14-34-2-4W	North Reference:	Grid
Well:	14-34-2-4W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	
10,500.0	0.00	0.00	10,488.0	358.4	-16.1	358.8	0.00	0.00	0.00	
10,600.0	0.00	0.00	10,588.0	358.4	-16.1	358.8	0.00	0.00	0.00	
10,700.0	0.00	0.00	10,688.0	358.4	-16.1	358.8	0.00	0.00	0.00	
10,800.0	0.00	0.00	10,788.0	358.4	-16.1	358.8	0.00	0.00	0.00	
10,900.0	0.00	0.00	10,888.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,000.0	0.00	0.00	10,988.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,100.0	0.00	0.00	11,088.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,200.0	0.00	0.00	11,188.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,300.0	0.00	0.00	11,288.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,400.0	0.00	0.00	11,388.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,500.0	0.00	0.00	11,488.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,600.0	0.00	0.00	11,588.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,700.0	0.00	0.00	11,688.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,800.0	0.00	0.00	11,788.0	358.4	-16.1	358.8	0.00	0.00	0.00	
11,862.0	0.00	0.00	11,850.0	358.4	-16.1	358.8	0.00	0.00	0.00	

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (m)	Easting (m)	Latitude	Longitude	
- hit/miss target										
- Shape										
BHL	0.00	360.00	11,850.0	358.4	-16.1	1,381,578.32	-1,892,445.03	40° 15' 30.642 N	110° 19' 23.601 W	
- plan hits target center										
- Point										

AFFIDAVIT OF SURFACE OWNERSHIP AND SURFACE USE

Peter Burns personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Peter Burns. I am a Land Associate for Newfield RMI LLC ("Newfield RMI"), whose address is 1001 17th Street, Suite 2000, Denver, CO 80202.
2. Newfield Production Company ("Newfield") is the Operator of the proposed Gilbert 14-34-2-4W well with a surface location to be positioned in the SESW of Section 34, Township 2 South, Range 4 West, Duchesne County, Utah (the "Drillsite Location").
3. Pursuant to that certain Special Warranty Deed dated June 20, 2012 from Alpine Partners, a Utah General Partnership, to Newfield RMI, recorded in Book A649, Page 533, and Document # 446789 of the official records of Duchesne County, Utah, Newfield RMI is the surface owner of the Drillsite Location.
4. Newfield has the right to construct and operate the Gilbert 14-34-2-4W Drillsite Location.

FURTHER AFFIANT SAYETH NOT.



Peter Burns

ACKNOWLEDGEMENT


STATE OF COLORADO §
CITY AND §
COUNTY OF DENVER §

Before me, a Notary Public, in and for the State, on this 4th day of October, 2012, personally appeared Peter Burns, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.




NOTARY PUBLIC

My Commission Expires:




My Commission Expires February 09, 2013

Typical 5M BOP stack configuration



Typical 5M choke manifold configuration





October 4, 2012

State of Utah
Division of Oil, Gas & Mining
ATTN: Brad Hill
P O Box 145801
Salt Lake City, UT 84114

RE: **Gilbert 14-34-2-4W**
Section 34, T2S, R4W
Duchesne County, Utah

Dear Brad,

Newfield Production Company proposes to drill the Gilbert 14-34-2-4W from a surface location of 301' FSL & 2,085' FWL of Section 34, T2S, R4W. Newfield shall case and cement the Gilbert 14-34-2-4W wellbore from the surface location to the point where the wellbore reaches the legal setback of 660' FSL of Section 34, T2S, R4W. The cased and cemented portion of the wellbore shall not be perforated nor produced. In the event a future recompletion into the cased and cemented portion of the wellbore is proposed, Newfield shall file the appropriate application with the State. Due to these circumstances, Newfield respectfully requests that DOGM administratively grant an exception location for the Gilbert 14-34-2-4W.


If you have any questions or require further information, please do not hesitate to contact the undersigned at 303-383-4169 or by email at kharris@newfield.com. Your consideration of this matter is greatly appreciated.

Sincerely,

A handwritten signature in blue ink, appearing to read "Ken H.", written over a large, diagonal red "CONFIDENTIAL" watermark.

Kenneth M. Harris
Landman

RECEIVED: October 09, 2012

NEWFIELD EXPLORATION COMPANY**PROPOSED LOCATION LAYOUT****14-34-2-4W****3-3-3-4W***Pad Location: SESW Section 34, T2S, R4W, U.S.B.&M.*

SURVEYED BY: C.S.	DATE SURVEYED: 06-20-12	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 06-21-12	V1
SCALE: 1" = 60'	REVISED:	

Tri State

(435) 781-2501

Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078





NEWFIELD EXPLORATION COMPANY

CROSS SECTIONS

14-34-2-4W

3-3-3-4W

Pad Location: SESW Section 34, T2S, R4W, U.S.B.&M.



NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1



ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	16,260	16,240	Topsoil is not included in Pad Cut Volume	20
PIT	4,330	0		4,330
TOTALS	20,590	16,240	2,810	4,350

SURVEYED BY: C.S.	DATE SURVEYED: 06-20-12	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 06-21-12	V1
SCALE: 1" = 60'	REVISED:	


Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 09, 2012

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****14-34-2-4W****3-3-3-4W***Pad Location: SESW Section 34, T2S, R4W, U.S.B.&M.*



SURVEYED BY: C.S.	DATE SURVEYED: 06-20-12	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 06-21-12	V1
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078



API Number: 4301351781
Well Name: Gilbert 14-34-2-4W
Township T02.0S Range R04.0W Section 34
Meridian: UBM
Operator: NEWFIELD PRODUCTION COMPANY
Map Prepared:
Map Produced by Diana Mason

Units	Wells Query
STATUS	Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
Fields	TA - Temp. Abandoned
Unknown	TW - Test Well
ABANDONED	WDW - Water Disposal
ACTIVE	WW - Water Injection Well
COMBINED	WSW - Water Supply Well
INACTIVE	Bottom Hole Location - Oil/Gas/Dls
STORAGE	
TERMINATED	



Well Name	NEWFIELD PRODUCTION COMPANY Gilbert 14-34-2-4W 430135178			
String	Cond	Surf	I1	Prod
Casing Size(")	14.000	9.625	7.000	4.500
Setting Depth (TVD)	60	1000	9450	11838
Previous Shoe Setting Depth (TVD)	0	60	1000	9450
Max Mud Weight (ppg)	8.3	8.3	9.5	11.5
BOPE Proposed (psi)	0	500	5000	5000
Casing Internal Yield (psi)	1000	3520	9950	10690
Operators Max Anticipated Pressure (psi)	6778			11.0

Calculations	Cond String	14.000	"
Max BHP (psi)	.052*Setting Depth*MW=	26	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	19	NO <input type="text" value="diverter"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	13	NO <input type="text" value=""/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	13	NO <input type="text" value=""/>
Required Casing/BOPE Test Pressure=		60	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	Surf String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	432	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	312	YES <input type="text" value="diverter"/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	212	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	225	NO <input type="text" value="OK"/>
Required Casing/BOPE Test Pressure=		1000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	4668	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3534	YES <input type="text" value=""/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2589	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2809	NO <input type="text" value="Reasonable"/>
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1000	psi *Assumes 1psi/ft frac gradient

Calculations	Prod String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	7079	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	5658	NO <input type="text" value=""/>
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	4475	YES <input type="text" value="OK"/>
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	6554	YES <input type="text" value=""/>
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		9450	psi *Assumes 1psi/ft frac gradient

43013517810000 Gilbert 14-34-2-4W

Casing Schematic



Well name:	43013517810000 Gilbert 14-34-2-4W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Surface	Project ID: 43-013-51781
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 432 ft

Burst

Max anticipated surface pressure: 880 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,000 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 877 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 9,450 ft
Next mud weight: 9.500 ppg
Next setting BHP: 4,664 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,000 ft
Injection pressure: 1,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1000	9.625	36.00	J-55	LT&C	1000	1000	8.796	8177
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	433	2020	4.668	1000	3520	3.52	36	453	12.58 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: December 4, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1000 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013517810000 Gilbert 14-34-2-4W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Intermediate	Project ID: 43-013-51781
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 9.500 ppg
Internal fluid density: 1.000 ppg

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 206 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 3,757 ft

Burst

Max anticipated surface pressure: 4,468 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 6,547 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 8,108 ft

Directional Info - Build & Drop

Kick-off point 1000 ft
Departure at shoe: 359 ft
Maximum dogleg: 1 °/100ft
Inclination at shoe: 0 °

Re subsequent strings:

Next setting depth: 11,838 ft
Next mud weight: 11.500 ppg
Next setting BHP: 7,072 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 9,450 ft
Injection pressure: 9,450 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9462	7	26.00	P-110	LT&C	9450	9462	6.151	98357
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4173	6230	1.493	6547	9950	1.52	245.7	693	2.82 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: December 4, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9450 ft, a mud weight of 9.5 ppg. An internal gradient of .052 psi/ft was used for collapse from TD to Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	43013517810000 Gilbert 14-34-2-4W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Production Liner	Project ID: 43-013-51781
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 11.500 ppg
Internal fluid density: 1.000 ppg

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 240 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 9,938 ft

Burst

Max anticipated surface pressure: 4,468 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 7,072 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 11,412 ft

Liner top: 9,262 ft

Directional Info - Build & Drop

Kick-off point 1000 ft
Departure at shoe: 359 ft
Maximum dogleg: 0 °/100ft
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2550	4.5	11.60	P-110	LT&C	11838	11850	3.875	12286
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	6457	7580	1.174	7072	10690	1.51	29.6	279	9.43 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: December 4, 2012
Salt Lake City, Utah

Remarks:

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 11838 ft, a mud weight of 11.5 ppg. An Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Gilbert 14-34-2-4W
API Number 43013517810000 **APD No** 6990 **Field/Unit** ALTAMONT
Location: 1/4,1/4 SESW **Sec** 34 **Tw** 2.0S **Rng** 4.0W 301 FSL 2085 FWL
GPS Coord (UTM) 557468 4456560 **Surface Owner** Newfield RMI LLC

Participants

Tim Eaton, Forrest Bird, Zander McIntyre - Newfield

Regional/Local Setting & Topography

This location is situated just below (2.5 miles South) the town of Upalco and Sand Wash Reservoir just below the top of the Bench on a flat knolly terrace. The soils are silty clayey sands with some exposed gypsum and rounded clastic gravels. The surrounding lands are highly eroded and slopes to flood plain below are quite steep. The location is proposed on top of a deeply incised erosional swale. The surface is moderately vegetated with Ephedra, Opuntia, Atriplex and Galletta. Cottonwoods and other indicator species are found immediately adjacent. A mapped wash with Riparian vegetation is found North and drains to a named wetland.

No wildlife or cultural resources were noted during the visit. The area has not been previously disturbed or used for grazing, agriculture or industrial purposes though future development for petroleum extraction is planned for the near future. The Lake Fork River and Zimmerman Wash are found in the floodplain below and East of location.

Surface Use Plan

Current Surface Use

Grazing

New Road Miles

0.4922

Well Pad

Width 300 Length 400

Src Const Material

Onsite

Surface Formation

UNTA

Ancillary Facilities

Waste Management Plan Adequate?

Y

Environmental Parameters

Affected Floodplains and/or Wetlands

N

wetland/ riparian vegetation present onsite

Flora / Fauna

High desert shrubland ecosystem. Expected vegetation consists of black sagebrush, shadscale, Atriplex spp., mustard spp, rabbit brush, horsebrush, broom snakeweed, Opuntia spp and spring annuals.

Dominant vegetation;

Galletta, Pinion pine and Ephedra surround the proposed site.

Wildlife;

Adjacent habitat contains forbs that may be suitable browse for deer, antelope, prairie dogs or rabbits, though none were observed.

Soil Type and Characteristics

gravely clasts in a silty grey clay heavily incised, sloping East

Erosion Issues Y

location is highly eroded and incised as is surrounding lands

Sedimentation Issues Y

Evidence of sediment transport is evident and abundant

Site Stability Issues Y

poor soil types for structural purposes

Drainage Diversion Required? Y

site is bordered on all four sides by drainages that lead to a wetland thorough areas with riparian vegetation

Berm Required? Y**Erosion Sedimentation Control Required? Y**

concerns for corners 6 7 and 8 touching a major drainage

Paleo Survey Run? Y Paleo Potential Observed? N Cultural Survey Run? Y Cultural Resources? N

Reserve Pit**Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)	25 to 75	15
---------------------------------------	----------	----

Distance to Surface Water (feet)		20
---	--	----

Dist. Nearest Municipal Well (ft)	>5280	0
--	-------	---

Distance to Other Wells (feet)	>1320	0
---------------------------------------	-------	---

Native Soil Type	Mod permeability	10
-------------------------	------------------	----

Fluid Type	Fresh Water	5
-------------------	-------------	---

Drill Cuttings	Normal Rock	0
-----------------------	-------------	---

Annual Precipitation (inches)		0
--------------------------------------	--	---

Affected Populations

Presence Nearby Utility Conduits	Not Present	0
---	-------------	---

Final Score	50	1 Sensitivity Level
--------------------	----	---------------------

Characteristics / Requirements

A 140' x 100' x 10' deep reserve pit is planned in an area of cut on the northwest side of the location. A pit liner is required. Newfield commonly uses a 30 mil liner with a felt underliner. Pit should be fenced to prevent entry by deer, other wildlife and domestic animals. Pit to be closed within one year after drilling activities are complete.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 30 Pit Underlayment Required? Y

Other Observations / Comments

API Well Number: 43013517810000

very tall fill slopes on corners 8, 1, 4, and 7. access road fill will block drainage from corner 6.
Corner 6 to be rounded

Chris Jensen
Evaluator

11/14/2012
Date / Time

CONFIDENTIAL

RECEIVED: December 11, 2012

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner CBM
6990	43013517810000	LOCKED	OW	P No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Newfield RMI LLC
Well Name	Gilbert 14-34-2-4W		Unit	
Field	ALTAMONT		Type of Work	DRILL
Location	SESW 34 2S 4W U 301 FSL 2085 FWL GPS Coord (UTM) 557461E 4456560N			

Geologic Statement of Basis

Newfield proposes to set 60 feet of conductor and 1,000 feet of surface casing both of which will be cemented to surface. The surface and intermediate holes will be drilled utilizing air/fresh water mud. The estimated depth to the base of moderately saline ground water is 2,500 feet. A search of Division of Water Rights records indicates that there are 7 water wells within a 10,000 foot radius of the center of Section 34. Only 1 well is located within 1 mile of the proposed well. The wells range between 325 and 1,000 feet in depth and are used for irrigation, stock watering, domestic and oilfield purposes. Intermediate casing cement should be brought up to or above the base of the moderately saline ground water in order to isolate it from fresher waters up hole.

Brad Hill
APD Evaluator

11/26/2012
Date / Time

Surface Statement of Basis

Location is proposed in a good location although outside the spacing window. Well is planned as a directional well and the producing bottom of hole is within the spacing window. Access road enters the pad from the North and will impede the flows from an existing drainage. A culvert of sufficient size is to be appropriately placed. The Operator is, in this case, the landowner and its representative was in attendance for the pre-site inspection.

The soil type and topography at present do combine to pose a significant threat to erosion or sediment/ pollution transport in these regional climate conditions.

Construction standards of the Operator do not appear to be adequate for the proposed purpose as submitted. Plans lack measures for importing materials, using a geogrid or compacting native soils to improve stability. Deep fill slopes are planned near and alongside a drainages of significant size. Operator came to the onsite with no plans for protection of slopes but, agreed armoring with rip rap and other BMP's are warranted on corners 7 & 8 and the corner 6 is to be rounded to prevent slopes from being eroded downstream to wetland / riparian area.

I recognize no special flora or animal species or cultural resources on site that the proposed action may harm. A riparian area can be found adjacent the site to the East and North. The location was previously surveyed for cultural and paleontological resources as the operator saw fit. I have advised an ESA consultation to be initiated to insure no disturbance to TES species that may have not been seen during onsite visit from either the diversions nor disturbance.

The location should be bermed to prevent spills from leaving the confines of the pad.

Fencing around the reserve pit will be necessary once the well is drilled to prevent wildlife

and livestock from entering. A synthetic liner of 30 mils (minimum) should be utilized in the reserve pit. Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues. No diversion is thought to be warranted in this case. Care to be taken that overland flows do not impact or erode topsoil pile near corners 8,1 & 2 or topsoils will need to be stored elsewhere onsite. Plans to be resubmitted as a sundry reflecting these changes.

Chris Jensen
Onsite Evaluator

11/14/2012
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 30 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	Compaction and armoring with rip rap of fill slopes. See corners 7,8,1,and 4 on North and East sides. Corner 6 to be rounded and access road to have culvert installed.
Surface	Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 10/9/2012

API NO. ASSIGNED: 43013517810000

WELL NAME: Gilbert 14-34-2-4W

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: SESW 34 020S 040W

Permit Tech Review: ☒

SURFACE: 0301 FSL 2085 FWL

Engineering Review: ☒

BOTTOM: 0660 FSL 2076 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.25753

LONGITUDE: -110.32429

UTM SURF EASTINGS: 557461.00

NORTHINGS: 4456560.00

FIELD NAME: ALTAMONT

LEASE TYPE: 4 - Fee

LEASE NUMBER: Patented

PROPOSED PRODUCING FORMATION(S): GREEN RIVER-WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

LOCATION AND SITING:

☒ PLAT☐ R649-2-3.☒ Bond: STATE/FEE - B001834

Unit:

☐ Potash☐ R649-3-2. General☐ Oil Shale 190-5☐ Oil Shale 190-3☒ R649-3-3. Exception☐ Oil Shale 190-13☒ Drilling Unit☒ Water Permit: 437478

Board Cause No: Cause 139-90

☐ RDCC Review:

Effective Date: 5/9/2012

☒ Fee Surface Agreement

Siting: 4 Producing Grrv-Wstc Wells In Sec Drl Unit

☐ Intent to Commingle☒ R649-3-11. Directional Drill

Commingle Approved

Comments: Presite Completed

Stipulations: 1 - Exception Location - bhill
5 - Statement of Basis - bhill
10 - Cement Ground Water - hmacdonald
15 - Directional - dmason
25 - Surface Casing - hmacdonald

RECEIVED: December 11, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Gilbert 14-34-2-4W
API Well Number: 43013517810000
Lease Number: Patented
Surface Owner: FEE (PRIVATE)
Approval Date: 12/11/2012

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-90. The expected producing formation or pool is the GREEN RIVER-WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

The 5 ½" casing string cement shall be brought back to ±800' to isolate base of moderately saline ground water.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

Approved By:

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Patented			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000, Denver, CO, 80202		8. WELL NAME and NUMBER: Gilbert 14-34-2-4W			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0301 FSL 2085 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 34 Township: 02.0S Range: 04.0W Meridian: U		9. API NUMBER: 43013517810000			
PHONE NUMBER: 303 382-4443 Ext		9. FIELD and POOL or WILDCAT: ALTAMONT			
COUNTY: DUCHESNE		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/15/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="vertical-align: top; width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="vertical-align: top; width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="vertical-align: top; width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. This sundry is being submitted to request an extension to this APD that expires on 12/11/2013.					
Approved by the Utah Division of Oil, Gas and Mining Date: November 18, 2013 By:					
NAME (PLEASE PRINT) Melissa Luke		PHONE NUMBER 303 323-9769			
SIGNATURE N/A		TITLE Regulatory Technician			
DATE 11/13/2013					



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013517810000

API: 43013517810000

Well Name: Gilbert 14-34-2-4W

Location: 0301 FSL 2085 FWL QTR SESW SEC 34 TWP 020S RNG 040W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 12/11/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Melissa Luke

Date: 11/13/2013

Title: Regulatory Technician **Representing:** NEWFIELD PRODUCTION COMPANY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Patented
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000 , Denver, CO, 80202		8. WELL NAME and NUMBER: Gilbert 14-34-2-4W
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0301 FSL 2085 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 34 Township: 02.0S Range: 04.0W Meridian: U		9. API NUMBER: 43013517810000
PHONE NUMBER: 303 382-4443 Ext		9. FIELD and POOL or WILDCAT: ALTAMONT
COUNTY: DUCHESNE		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/15/2014	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"><input type="checkbox"/> ACIDIZE</div> <div style="width: 33%;"><input type="checkbox"/> ALTER CASING</div> <div style="width: 33%;"><input type="checkbox"/> CASING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TUBING</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL NAME</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL STATUS</div> <div style="width: 33%;"><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div style="width: 33%;"><input type="checkbox"/> CONVERT WELL TYPE</div> <div style="width: 33%;"><input type="checkbox"/> DEEPEN</div> <div style="width: 33%;"><input type="checkbox"/> FRACTURE TREAT</div> <div style="width: 33%;"><input type="checkbox"/> NEW CONSTRUCTION</div> <div style="width: 33%;"><input type="checkbox"/> OPERATOR CHANGE</div> <div style="width: 33%;"><input type="checkbox"/> PLUG AND ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> PLUG BACK</div> <div style="width: 33%;"><input type="checkbox"/> PRODUCTION START OR RESUME</div> <div style="width: 33%;"><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div style="width: 33%;"><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div style="width: 33%;"><input type="checkbox"/> TEMPORARY ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> TUBING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> VENT OR FLARE</div> <div style="width: 33%;"><input type="checkbox"/> WATER DISPOSAL</div> <div style="width: 33%;"><input type="checkbox"/> WATER SHUTOFF</div> <div style="width: 33%;"><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div style="width: 33%;"><input checked="" type="checkbox"/> APD EXTENSION</div> <div style="width: 33%;"><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div style="width: 33%;"><input type="checkbox"/> OTHER</div> </div>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	
<input type="checkbox"/> SPUD REPORT Date of Spud:	
<input type="checkbox"/> DRILLING REPORT Report Date:	
OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 This sundry notice is being submitted to request an extension to this APD that expires on 12/11/2014.

Approved by the
November 05, 2014
Oil, Gas and Mining

Date: _____

By:

NAME (PLEASE PRINT) Melissa Luke	PHONE NUMBER 303 323-9769	TITLE Regulatory Technician
SIGNATURE N/A	DATE 11/3/2014	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013517810000

API: 43013517810000

Well Name: Gilbert 14-34-2-4W

Location: 0301 FSL 2085 FWL QTR SESW SEC 34 TWP 020S RNG 040W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 12/11/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Melissa Luke

Date: 11/3/2014

Title: Regulatory Technician Representing: NEWFIELD PRODUCTION COMPANY



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 24, 2015

Newfield Production Company
Rt 3 Box 3630
Myton, UT 84052

Re: APDs Rescinded for Newfield Production Company,
Duchesne and Uintah County


Ladies and Gentlemen:

Enclosed find the list of APDs that is being rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded effective December 24, 2015

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
Brad Hill, Technical Service Manager
SITLA, Ed Bonner



43-047-52434 GMBU 3-36-8-18H
43-013-51750 Shields 1-30-3-2WH
43-013-51781 Gilbert 14-34-2-4W
43-013-51728 Slade 2-25-2-2WH